

## Harlow Home Design Custom Home & Remodeling

Cell: 207-739-0673 . . . Email: mharlow@harlowhomedesign.com

### InSoFast EX 2.5 Foundation & Exterior Wall Insulation

InSoFast EX 2.5 (R-10) Insulation - Installed with No Drywall  
(See Specifications below)

#### **Optional Plus+ Wall Insulation:**

**If local code requires R-15 continuous foundation insulation, Plus+ Wall will exceed this requirement. It consists of 1-layer InSoFast EX 2.5 (R-10) & 1-layer Owens Corning Foamular (R-3) which is R-15.58 continuous, installed with NO drywall.**

#### EX 2.5 Panel Features & Specifications:

Thickness	2.5"
Width x Height	2' x 4'
Continuous Closed-Cell Insulation	R-10
Comparable Performance to **	2x4 Wall/R-15 Batts
Fully Insulated Composite Studs (at 16" O.C.)	Recessed 1/2" Below Surface
Tongue and Groove Interlocking Edges	✓
Cutting Indicator Lines	✓
Electrical Raceways at Code Depth	✓
Drywall and Finish Ready	✓
Designed for Basements	✓
Moisture Drainage Channels on Back	✓
Qualifies as Continuous Insulation	✓
Nationwide Code Compliance (US & Canada) CCRR-1029	✓
Rain Screen Technology on Front	✓
Designed for Siding and Exterior Finishes	✓

#### EX 2.5 Panels



#### Installed Price

Call for latest pricing  
& Free Estimate . . . . .

Call for latest pricing  
& Free Estimate . . . . .

\*\* Oak Ridge National Laboratory

- Taxes included in above pricing -